

**BUSINESS CENTER SOUTH
THE NEVADA SYSTEM OF HIGHER EDUCATION (“NSHE”), ON BEHALF OF NEVADA
STATE COLLEGE (“NSC”)**

ADDENDUM 2 TO INVITATION FOR BID NO. 5193-KO

AUDIOVISUAL SYSTEMS AND INSTALLATION FOR NEVADA STATE COLLEGE

**University of Nevada, Las Vegas
Purchasing Department
4505 Maryland Parkway
Las Vegas, Nevada 89154-1033
(702) 895-3521**

Date of Release: April 27, 2015

Date and Hour of Bid Opening: May 1, 2015 @ 3:00 PM Local Time

The following additions, deletions, clarifications and/or changes shall be made and incorporated in the subject Invitation For Bid, IFB 5193-KO.

The Completion dates for the project have been extended and all references in the Invitation To Bid regarding the Project completion dates shall be amended as follows:

Reference: Section D Scope of Work/Specifications, Page 16, No. 2 Project Completion Date: This section shall be removed in its entirety and replaced with the following.

The Completion dates for this project have been extended. The Completion of this Project must be no later than, Monday, July 6, 2015 for the NSE Building and no later than Friday, July 24, 2015 for the SAA Building.

Reference Exhibit A Pricing Response Form, Page 22, No. 2: This section shall be removed in its entirety and replaced with the following:

The Completion dates for this project have been extended. The Completion of this Project must be no later than, Monday, July 6, 2015 for the NSE Building and no later than Friday, July 24, 2015 for the SAA Building.

Reference Exhibit G Schedule Response Form:

The Installation for the NSE building is scheduled to be completed no later than Friday June 26, 2015, shall be deleted and replaced with The Installation for the NSE building is scheduled to be completed no later than Monday, July 6, 2015.

The Installation for the SAA building is scheduled to be completed no later than Friday July 17, 2015 shall be deleted and replaced with The Installation for the SAA building is scheduled to be completed no later than Friday July 24, 2015.

Reference Exhibit L, Tab A-NSC Total Cost Estimate: The required completion date for NSE building is 6/26/15 shall be deleted and replaced with the required completion date for the NSE building in July 6, 2015.

Reference Exhibit L, Tab B-SAA Total Cost Estimate: The required completion date for the SAA building is 7/17/15 shall be deleted and replaced with the required completion date for the SAA building is July 24, 2015.

Clarifications

1. **Projector Lifts in SAA Meeting Rooms 135 –**
Delete the Draper SL4 projector lifts in the SAA Meeting rooms 135. Provide an appropriate pipe and projector mount in lieu of the deleted lifts. Please note that there is a large amount of HVAC ducting and other obstructions in some areas where the projector will need to mount so the AV Contractor will need to provide any necessary hardware to trapeze around the obstructions.
2. **Student Activities Building – It was brought to NSC's attention on the site walk that in certain areas of the Student Activities Building, speakers won't fit in ceiling.**
We are still working on a solution to this. Bidders should include the speakers as shown in the plans as an allowance. Speakers in the low soffit areas may change to a slimmer model post bid.
3. **Display Models – Samsung - option to switch to different model. It was mentioned that there would be a clarification on this during the site walk.**

Current drawings and specifications indicate Samsung models with HDBaseT input cards. These models will work, but will require the LAN port of the input card to be connected with a short cat5e cable to the LAN port on the display itself to enable control over the display functions. Contractors may submit using the existing models with this additional step required, or may submit using the alternative Panasonic displays listed below. The Panasonic models include a built-in HDBaseT port which enables direct digital video input and control with no further connections or input cards required.

Specified Model	Alternate Model
Samsung DH48D	Panasonic TH-47LF60
Samsung DH55D	Panasonic TH-55LF60

4. **No conduit in the following areas:** As a follow up to the pre-bid site walk, as observed, there is no conduit in place in the following areas and the AV Contractor shall be responsible for any pathways within walls as needed for installation of the AV equipment. This shall include any necessary patching and painting:
 - a. SAA Building Level 2 – Room Scheduler touch panels
 - b. SAA Building Level 2 – Training Lab 236, wall mounted displays

The following questions were raised and are answered below:

1. Owner-furnished Smartboards are or are not going to be covered under the warranty for this project?

Answer: This will apply to all OFE items, not necessarily just the Smartboards:

a. AV Contractor shall inspect and test all owner furnished equipment in its existing installed locations. AV Contractor shall make a written report of any malfunctioning, broken or missing parts to the owner prior to moving owner furnished equipment to its new location.

b. AV Contractor shall provide a 1 year warranty only on AV Contractor's installation of the OFE equipment. Equipment warranty shall only include the remaining term of the original manufacturer's warranty, if any still remains.

2. Can you please provide a project schedule? – Primavera format.

Answer: The General Contractor should be substantially complete prior to the start of the AV installation. Bid Opening is scheduled for May 1, 2015 as stated in the original bid invitation. Anticipated award is approximately 2 weeks after bid opening. Please refer to the new AV installation completion dates for each building included in this addendum. Winning Contractor shall submit their own schedule for approval as indicated in the specifications.

3. Per Aver, the SPB350+ document cam is a discontinued item. PL50 is their current model available. Please advise if the PL50 is an acceptable substitution.

Answer: Yes, this model is the current in Aver's lineup and is acceptable.

4. I need clarification on the wireless mic system mentioned for the classroom. DWG AV9.01 shows a receiver package (Shure ULXD4D) but nowhere is there mention of the transmitters that should go with it. The spec calls out a single receiver with 2 transmitters (one lapel and one handheld) which is a contradiction to the ULXD4D, which is 2 receivers and no transmitters. Also, the one-line diagrams do not show a wireless receiver rather they show a cable made available to hook a receiver up, which contradicts the rack elevation which shows a fixed product.

Answer: Specification sections which refer to a "single channel" wireless mic are inaccurate and shall be replaced with the term "dual channel". Please refer to the Bill Of Materials for the model of the transmitters. Refer to the Bill Of Materials for rooms with permanently installed wireless systems. Bill Of Materials Alternate 2 provides an explanation of the rest of the question. Contractor shall wire all classrooms as shown on the drawings to accept wireless mic receivers shown in Alternate 2.

5. Can you provide a copy of the specifications for the SI lectern/station?

Answer: Refer to drawing AV9.01 for a drawing and rack elevations of the lecterns. Lecterns are Spectrum Industries "Freedom Lectern XRS" with overbridge and an additional 15RU rolling rack from Spectrum.

6. We have a discrepancy with the projectors. The model specified is a Panasonic PT-RW430UW and my research confirms it is a 3500 unit. The spec on page 6, section 2 calls for a projector that is either a 4500 or 6500 lumen unit depending on the room size. The spec on page 4 Section j-1-g says to use the greater value.

Answer: Please provide all models as specified in the drawings and Bill Of Materials.

7. Should the Control System be Creston or AMX?

Answer: We are open to either of these. The room management must be cloud hosted.

8. Can you provide a Construction schedule?

Answer: Please see answer to question 2 above.

9. Can you provide a training schedule?

Answer: AV Contractor shall schedule training with the owner shortly after completion of installation.

10. Per the Invitation to Bid, the completion dates are specified as the 26th and 17th. Does this mean the training should be completed by this date?

Answer: Training can occur after completion. Please note that the project completion dates have been extended as follows: Monday, July 6, 2015 for the NSE Building and no later than Friday, July 24, 2015 for the SAA Building.

11. Are there liquidated damages for this project?

Answer: There are no liquidated damages for this project.

12. Will Contractor be required to sleeve and fire-caulk the IDF room?

Answer: The walls are not rated so the Contractor will NOT be required to sleeve and fire-caulk the IDF rooms.

13. Will Ledcor be responsible for mounting projector screens?

Answer: All projector screens are provided and installed by others. AV Contractor shall be responsible for installation and termination of control cabling to the projection screens.

14. Is there a way to get an equipment list for the Finance Lab, NESE 12?

Answer: Most if not all of the equipment for the lab was included in the bid documents, including photos and diagrams. There should be enough information already included in the Invitation to Bid for bidders to provide a bid.

ALL OTHER TERMS, CONDITIONS AND SPECIFICATIONS OF THIS INVITATION TO BID REMAIN THE SAME.